### Retaining Wall 6.50L Geotechnical Design Memorandum

WSDOT I-405 Renton to Bellevue Widening and Express Toll Lanes
Renton to Bellevue, Washington

November 30, 2021

WSDOT Contract No. 9242 Terracon Project No. 81215044

Prepared for:

**Parsons** 

Prepared by:

Terracon Consultants, Inc. Mountlake Terrace, Washington

terracon.com



Environmental Facilities Geotechnical Materials



#### **Revision History**

Date	Revision
10/29/21	IR-CR
11/29/21	Final

Terracon Consultants, Inc. 21905 64th Ave. W., Ste. 100 Mountlake Terrace, WA 98043 P [425] 771-3304 F [425] 771-3549 terracon.com



November 30, 2021

Parsons Transportation Group 600 University Street, Suite 700 Seattle, WA 98101

Attn: Mr. Paul Dickman P: (602) 284-3609

E: <u>paul.dickman@parsons.com</u>

RE: Retaining Wall 6.50L

I-405 Renton to Bellevue Widening and Express Toll Lanes Project

I-405 MP 0.0 to 14.6 King County, WA

WSDOT Contract No. 9242 Terracon Project No. 81215044

Dear Mr. Dickman:

Terracon Consultants, Inc. (Terracon) is pleased to present this Geotechnical Design Memorandum for Wall 6.50L as part of the above referenced project. This report presents our analyses and recommendations for design and construction of the soil nail and special barrier walls.

The information evaluated for this report includes data presented in the Request for Proposal (RFP) Documents, prior exploration and geotechnical work completed by Wood Environment and Infrastructure Solutions, Inc (Wood). This report was prepared in accordance with the requirements of RFP Section 2.6.5.3 of the project Technical Requirements. Geotechnical design was performed in accordance with the project Mandatory Standards identified in Section 2.6.2 of the project Technical Requirements current version at the time of award.

We appreciate the opportunity to be of service to Parsons and the Flatiron-Lane Joint Venture. Please let us know if you have any questions regarding this design information.

Sincerely,

**Terracon Consultants, Inc.** 

Yashar Yasrobi, P.E. Project Engineer

Pete Palmerson, P.E. Geotechnical Department Manager

Terracon Consultants, Inc. 21905 64th Ave. W., Ste. 100 Mountlake Terrace, WA 98043 P [425] 771-3304 F [425] 771-3549 terracon.com

#### Wall 6.50L Geotechnical Tech Memo



I I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

#### **TABLE OF CONTENTS**

1.0	DESCRIPTION1						
2.0	PLANNED CONSTRUCTION1						
3.0	PROJECT GEOLOGY AND SOIL CONDITIONS						
	3.1	Site Soil Conditions	2				
	3.2	Groundwater Conditions	2				
4.0	GEOL	OGIC HAZARDS	2				
	4.1 4.2	Seismic Site Class and Design ParametersLiquefaction					
5.0	DESIG	ON SOIL PROPERTIES	3				
	5.1 5.2	Engineering Stratigraphic UnitsESU Design Soil Properties					
6.0	.0 GEOTECHNICAL ANALYSIS AND DESIGN RECOMMENDATIONS						
	6.1 6.2 6.3 6.4	Standard Barrier Design Parameters  Soil Nail Wall Analyses  Soil Nail Wall Recommendations  Global Stability	5 6				
7.0	CONS	STRUCTION CONSIDERATIONS	7				
8.0	GEOT	ECHNICAL INSTRUMENTATION PLAN	8				
9.0	GEOTECHNICAL SPECIAL INSPECTION PLAN						
10.0	Use of this Report10						
11.0							
APPE	PPENDIX A12						
APPE	NDIX B	B	.13				
APPE	NDIX C	,	.14				



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

# WALL 6.50L - GEOTECHNICAL DESIGN MEMO I-405 Renton to Bellevue Design-Build Renton to Bellevue, Washington

WSDOT Contract No. 9242 Terracon Project No. 81215044 November 30, 2021

#### 1.0 DESCRIPTION

This Geotechnical Design Memorandum provides recommendations regarding the design and construction of Retaining Wall 6.50L. This report is based on our present knowledge of the proposed construction, the retaining wall plans as provided in Appendix A, coordination with other design disciplines and contractor's representatives on the project team.

#### 2.0 PLANNED CONSTRUCTION

The retaining wall plan and profile that form the basis of our design are shown in Appendix A: Retaining Wall Plans. As currently proposed, Wall 6.50L is a combination special design barrier and soil nail wall. The wall is located along on the west side of southbound I-405 to accommodate road widening at the NE 30<sup>th</sup> Street Overcrossing. Description of the wall characteristics are provided below in Table 1.

**TABLE 1 - WALL TYPE/DESCRIPTION** 

Retaining Wall ID	6.50L	
Туре	Special Barrier/Soil Nail Wall	
Begin Soil Nail Wall	SB405 STA 5646+03.79 (33.33' LT)- Wall STA 0+82.00	
End Soil Nail Wall	SB405 STA 5647+69.58 (33.80' LT)-Wall STA 2+50.00	
Soil Nail Wall Height (ft)	3.6 to 7.3	
Soil Nail Wall Length (ft)	165	
Special Design Barrier	North and South ends of soil nail wall, limits shown on roadway plans	
Special Design Barrier Max Height (ft)	Up 3.5	
Existing Borings	H-2-79, H-2-81, W-80-20	

#### 3.0 PROJECT GEOLOGY AND SOIL CONDITIONS

Upon review of the boring logs, the subsurface stragitgraphy was broken out into Engineering Stratigraphic (or Soil) Units (ESUs). ESUs are grouped together based on geologic origin, engineering soil properties and anticipated behavior with respect to the proposed improvments. For project consistency, we have continued the geologic unit descriptions and their identification as specific ESU as previously characterized by Wood, Hart Crowser and GeoEngineers. The



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

ESUs encountered at the subject site, along with a brief discussion of their descriptions used for the project geology are provided in Table 4. Engineering properties of the ESUs encountered are discussed in Section 5.

#### 3.1 Site Soil Conditions

Subsurface exploration data was provided in the Washington State Department of Transportation's (WSDOT's) Geotechnical Data Report (GDR). An additional exploration was advanced by Wood. The boring locations are shown on the plan view in Appendix A. A subsurface profile are presented Section 2 of the attached calculations. Copies of the boring logs are provided in Appendix B: Historic Borings. Table 2 summarizes the borings we considered for design of retaining wall 6.50L.

**TABLE 2 - BORING SUMMARY** 

Boring Number	Date Completed	Boring Depth (ft.)	Ground Surface Elevation (ft. MSL) <sup>1</sup>	Groundwater Elevation (ft. MSL)
W-80-20	6/4/2020	20.6	219.6	Dry
H-2-79	12/18/1979	47.9	224	192
H-2-81	3/7/1981	20	211.3	205.3

#### Notes:

#### 3.2 Groundwater Conditions

Groundwater was noted in two of the borings below the proposed improvements. The occurrence and elevation of groundwater is expected to be variable and to fluctuate seasonally due to variations in the amount of precipitation, evaporation, and surface water run-off. Our analyses used a groundwater elevation of 209 feet.

#### 4.0 GEOLOGIC HAZARDS

#### 4.1 Seismic Site Class and Design Parameters

Seismic design parameters for Wall 6.50L are based on the general procedure, as outlined in AASHTO LRFD Bridge Design Specifications (AASHTO) Section 3.10.2.1, are provided in Table 3 below. The parameters are based on a design seismic event with a seven percent probability of being exceeded in 75 years using the USGS National Hazard Maps (2014). The site coefficients have been modified in accordance with Section 4.2.3.1 of the BDM.

The weighted average Standard Penetration Test (SPT) blow count (blows per foot) for the borings, extrapolated to a depth of 100 feet of the soil profiles was used to determine the site

<sup>1.</sup> Ground surface elevations are rounded to the nearest 0.1 feet



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

class in accordance with the LRFD Bridge Design Specifications (AASHTO 2017). The results of the analyses indicate the site should be classified as Site Class D.

**TABLE 3 - SEISMIC DESIGN PARAMETERS** 

Parameter	Value
Site Class	D
Peak Ground Acceleration (PGA)	0.425g
FPGA	1.175
Site-Adjusted Peak Ground Acceleration (AS)	0.50
Mean Magnitude Earthquake (Mw)	7

The peak horizontal ground acceleration (PGA) for the Site Class B/C boundary recommended in Table 3 does not include amplification or damping due to the site soils. In order to assess seismic earth pressures and inertial effects on the wall, the PGA for Class B rock needs to be adjusted for the site soil conditions. We have used the site coefficients in the BDM to calculate an effective peak ground acceleration coefficient (As) of 0.50 to be used for liquefaction analyses. For seismic design of the walls as wells as the pseudostatic analy

#### 4.2 Liquefaction

Liquefaction is a phenomenon in which saturated cohesionless soils are subject to a temporary but essentially total loss of shear strength under the reversing, cyclic shear stresses associated with earthquake shaking.

Based on the depth to groundwater, the presence of cohesive soils and very dense glacial till at depth below the wall profile, we anticipate the liquefaction hazard to be low.

#### 5.0 DESIGN SOIL PROPERTIES

#### 5.1 Engineering Stratigraphic Units

Table 4 summarizes encountered geologic units and the assigned ESU used to develop recommendations for the retaining wall. As noted above, in the interest of maintaining consistency with previous work completed on the project we have adopted ESU units and descriptions used by Wood and adopted by Hart Crowser.

**TABLE 4 – ESU DESCRIPTION** 

Geologic Units	Assigned ESU	ESU Description
Fill	1B	Fill- Silty Sand and Gravel, medium dense to dense
Recessional Outwash	3B	Medium dense to very dense Sand
Lacustrine Deposits	3E	Stiff to very stiff-Silt/Clay



I-405 Renton to Bellevue Widening and Express Toll Lanes ■ Renton to Bellevue, WA November 30, 2021 ■ WSDOT Contract No. 9242 ■ Terracon Project No. 81205144

**TABLE 4 – ESU DESCRIPTION** 

Geologic Units	Assigned ESU	ESU Description
Glacial Till	4C	Dense to very dense Silty Sand and Gravel

A subsurface profile showing the relation ship of the wall to the ESU is shown in Appendix C.

#### 5.2 ESU Design Soil Properties

Table 5 presents the ESU soil properties, which were used in calculations for the soil nail and special barrier walls. Detailed calculations and procedures for determination of soil properties are provided in the attached calculations package. It is important to note the entire wall face and the bulk of the overburden consists of ESU 3B.

**TABLE 5 – DESIGN SOIL PROPERTIES** 

	Moist	DRAINE	D CONDITION	UNDRAINED CONDITION	
ESU	Unit Weight (PCF)	Friction Angle (degrees)	Cohesion (PSF)	Friction Angle (degrees)	Su <sup>i</sup> (PSF)
1B	125	35	50	35	200
3B	125	36	0	36	0
3E	120	32	50	0	1500
4C	135	40	200	40	200
Wall profile lies entirely within ESU 3B					

#### 6.0 GEOTECHNICAL ANALYSIS AND DESIGN RECOMMENDATIONS

#### 6.1 Standard Barrier Design Parameters

A special design barrier retaining up to 42 inches of soil is proposed beyond the soil nail limits for the north and south sections of wall. Table 6 below provides design parameters for the barrier based on the ESU 3B native soil which will be both the retained and foundation soil. Terracon has performed the global stability analyses and the structural engineer will perform the bearing, sliding and overturning analyses based on the values shown below

TABLE 6 - DESIGN PROPERTIES FOR SPECIAL BARRIER SECTION OF 6.50L

Retained/Bearing Soil (ESU 3B)	VALUE
Moist Unit Weight (PCF)	125
Friction Angle (DEG)	36
Active Earth Pressure Coefficient <sup>1</sup> , Ka (DIM)	0.35
M-O Earth Pressure Coefficient <sup>2</sup> , Kae (DIM)	0.79
Passive Earth Pressure Coefficient <sup>3</sup> , Kp (DIM)2	6.0
Sliding Coefficient <sup>4</sup> (DIM)	0.58
Minimum Embedment (FT)	1.0
Nominal Bearing Resistance <sup>5</sup> (KSF)	11
Service Limit State Bearing Resistance <sup>6, 7, 8</sup> (KSF)	13



I-405 Renton to Bellevue Widening and Express Toll Lanes ■ Renton to Bellevue, WA November 30, 2021 ■ WSDOT Contract No. 9242 ■ Terracon Project No. 81205144

#### Retained/Bearing Soil (ESU 3B)

**VALUE** 

- 1) Active EP for 2:1 backslope using Coulomb's method where  $\delta$ =2/3 $\phi$
- 2) Based on ½ As=0.25.
- 3) Passive EP for level toeslope using Coulomb's method where  $\delta=1/3\phi$
- 4) Sliding coefficient based on Eqn 10.6.3.4-2 in the AASHTO LRFD Bridge Design Specifications (assuming precast barrier)
- 5) Nominal bearing resistance must be factored by a resisitance factor of 0.45 for the Strength Limit State.
- 6) Resistance factor for the Service Limit State is 1.0.
- 7) Based on 1-inch of allowable settlement using Hough's method.
- 8) Based on 2.3 foot wide footing.

#### 6.2 Soil Nail Wall Analyses

Critical wall cross sections were selected for analysis using engineering judgment by taking into consideration existing soil conditions, wall geometry and surcharge loading. These critical sections were analyzed for internal stability, compound stability, and global stability. Five design sections were analyzed.

The analyses were performed using SnailPlus (DeepExcavation, LLC. 2021) using an ultimate pullout value of 20 psi (4.5 KIPS/FT) assuming a 6-inch diameter nail hole.

The soil nail analysis was performed using allowable stress design (ASD) with the following factors of safety:

- Temporary: Pullout FS = 2, Bar yield FS = 1.8, Soil Shear Strength Minimum FS = 1.35
- Permanent Static: Pullout FS = 2, Bar yield FS = 1.8, Soil Shear Strength Minimum FS =
   1.5
- Permanent Seismic: Pullout FS = 1.5, Bar yield FS = 1.35, Soil Shear Strength Minimum FS = 1.1

The soil nail analysis was completed with the following surcharge loads:

- Traffic = 250 psf uniform (outside the bridge footing)
- 2:1 Backslope (outside the bridge footing)
- NE 30<sup>th</sup> Street Bridge Pier 1 Foundation: 4.36 KSF uniform soil pressure acting over a 9 foot by 65 foot spread footing with the closest footing edge a horizontal distance of approximately 5 feet behind the wall face for the static case.
- NE 30<sup>th</sup> Street Bridge Pier 1 Foundation: 7.93 KSF uniform soil pressure acting over a 9 foot by 65 foot spread footing with the closest footing edge a horizontal distance of approximately 5 feet behind the wall face for the seismic case.



I-405 Renton to Bellevue Widening and Express Toll Lanes ■ Renton to Bellevue, WA November 30, 2021 ■ WSDOT Contract No. 9242 ■ Terracon Project No. 81205144

#### 6.3 Soil Nail Wall Recommendations

Based on the results of our analyses, we recommend the follow nail selection and pattern as outlined in Tables 7, 8 and 9. The top nail must be at least 2 feet below the ground surface behind the wall.

TABLE 7 - SOIL NAIL DESIGN STA 0+82 to 1+39

Minimum Nail	Horizontal	STATIC	SEISMIC	
Length (FT)	Spacing (FT)	Nail Head Load at Face (KIPS)	Nail Head Load at Face (KIPS)	
12	5	10.4	13.5	
Single row of nails in this section are #6, 75 KSI				

#### TABLE 8 - SOIL NAIL DESIGN STA 1+39 to 2+05

Minimum Nail	Horizontal	STATIC	SEISMIC
Length (FT)	Spacing (FT)	Nail Head Load at Face (KIPS)	Nail Head Load at Face (KIPS)
20	4	25	26.2

- 1. Two rows of nails, rectangular pattern in this section are #10, 75 KSI
- 2. Use nonstructural filler under bridge footing (unbonded zone)
- 3. Double corrosion protection required

TABLE 9 - SOIL NAIL DESIGN STA 2+05 to 2+50

Minimum Nail	Horizontal	STATIC	SEISMIC	
Length (FT)	Spacing (FT)	Nail Head Load at Face (KIPS)	Nail Head Load at Face (KIPS)	
12	5	10.2	12.9	
Single row of nails in this section are #6, 75 KSI				

Soil corrosivity in the nail zone is considered non-aggressive. Therefore, epoxy coated Grade 75 bar is specified for the entire wall. The WSDOT GDM requires that soil nail walls that are within the influence zone of spread footings be designed with double corrosion protection.

The soil nail length, reinforcement, and nail spacing presented in the tables above are the layouts required to achieve the minimum factors of safety required for the design.

#### 6.4 Global Stability

All wall sections were found to have an adequate factor of safety for global stability. Slide version 2 (Rocscience 2021) was used to model global stability with Spencer's and Bishop's method. In



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

the static case (Service I Limit State) surfaces were set to non-circular path search, with surface optimization selected.

Slide model output is presented in the following table. The GDM requires minimum factors of safety for global and compound stability of 1.3 in the static case, and 1.1 under seismic loading.

TABLE 10 - FACTORS OF SAFETY FOR GLOBAL STABILITY

Station	Static Factor of Safety	Pseudo-Static Factor of Safety
1+39.5	1.5	1.1
1+54	1.6	1.1
2+05	1.5	1.1
2+07	1.6	1.1
2+50	1.7	1.1

#### 7.0 CONSTRUCTION CONSIDERATIONS

Pre-fabricated drainage mat should be placed against the soil face in vertical strips between every column of nails prior to placing each lift of shotcrete. Strips should be overlapped between each lift to provide a continuous drainage path. During construction the wall drains discharge onto the subgrade in front of the wall. Once the wall is completed, the base of the drains should be directed to discharge through weep holes until the permanent drainage system is installed in front of the wall.

Proof tests have been called out and shall be performed on a number of test nails that is shown on the attached plans. Proof test nails shall not be production nails but shall be located within the production nail pattern and shall be evenly distributed across the face of the wall. We do not recommend performing nail testing under the bridge footing.

At least 1 successful verification test should be performed in the ESU 3B soil unit into which soil nails are to be installed prior to the installation of production nails. Proof and verification tests on soil nails shall be conducted in accordance with WSDOT Standard Specifications Section 6-15.3(8)A and B.

Section 15-3.4.2.1 of GDM requires the construction of a test pit to evaluate standup time at the excavation face. We recommend the contractor construct one test pit near the location of the verification test. The test pit will need to remain open for at least 24 hours The test pit should be a minimum of 10 feet deep and 15 feet long. Test pit should be constructed outside of the nail zone.

We recommend that temporary casing be used for nails constructed under the bridge footing and be backfilled with nonstructural filler such as Grout Type 4 for Mulitpurpose Applications as shown in the Standard Specificaitons 9-20.3(4).



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

#### 8.0 GEOTECHNICAL INSTRUMENTATION PLAN

The following bullet points identified in Section 2.6.7.5 requiring geotechnical instrumentation are either not currently proposed under the current work plan or not applicable to the project at the retaining wallscovered in this report:

- Sensitive facilities (none identified in RFP)
- Temporary Shoring (none currently proposed)
- Dewatering operations (none currently proposed)
- Staged embankment construction (not currently proposed)
- Ground structure vibrations during shaft casing or pile driving (no piles or casing currently proposed)
- Vibrations for freshly placed concrete (all concrete currently proposed as precast)

Should unanticipated conditions be encountered, or unanticipated construction means and methods be used that require additional geotechnical instrumentation, we will issue an addendum to this plan.

The soil nail retaining wall is planned to be constructed in front of the existing Pier 1 footing for the 30<sup>th</sup> Avenue Overcrossing. We recommend that wall facing be surveyed at approximate 50-foot intervals for vertical and horizontal monitoring purposes for the wall. In addition we recommend that the Pier 1 footing be surveyed at the north and south ends for monitoring of vertical and horizontal movement that may result as the proposed wall construction.

Survey information should be forwarded to the GER at regular intervals during construction of the walls.

#### 8.1 Alert and Action Levels

This GIP establishes limits of horizontal and vertical movements for alert and action levels for which additional consideration will be given to the construction of the soil nail retaining wall.

Alert Level Soil Nail Wall: Vertical movement of ½ inch. Horizontal movement of 1 inch.

**Action Level Soil Nail Wall:** Vertical movement of 1 inch. Horizontal movement of 3 inches.

Alert Level Pier 1 Footing: Vertical and horizontal movement of ½ inch.

**Action Level Pier 1 Footing:** Vertical and horizontal movement of ¾ inch.

At the point observed movement magnitudes reach the indicate values above the EOR, design team, and design-builder will be confer to incorporate the corrective action plan outlined below.



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

#### 8.2 Corrective Action Plan

The corrective action plan items below shall be implemented in accordance with Sections 2.6.7.1 and 2.6.7.5.1 and will include the following steps:

- Identification of the work areas where the action level has been reached
- Notify the EOR that action levels have been reached and corrective action is necessary
- Provide a revised work plan in consultation with the design team and designbuilder
- Provide a revised work plan to the WSDOT Engineer for Review and Comment
- Work in areas where action levels were reached will be halted until the revised work plan has been accepted by the WSDOT EOR
- Identify circumstances where the corrective actions were needed and revise the retaining wall design and/or incorporate revised construction procedures to keep observed settlements below the action level
- Notify the WSDOT EOR immediately when the observed movement meets or exceeds the allowable settlement and in writing within 24 hours

#### 9.0 GEOTECHNICAL SPECIAL INSPECTION PLAN

The project technical requirements require continuous construction inspection of soil nail installation and testing by a Geotechnical Special Inspector (GSI) or QA Inspection (QAI) Technician operating under the direction and review of the Geotechnical Engineer of Record. The construction inspection shall be reviewed by the Geotechnical Engineer-of-Record, or their representative, to confirm that subsurface conditions match design assumptions, facing installation conforms to the required reinforcement and shotcrete placement, and soil nail proof and verification tests meet the specified performance criteria.

The following shall be observed, verified, and documented by a GSI or a QAI:

- Types and locations of soil/rock units encountered during construction:
- Groundwater conditions during drilling; the types of equipment used to drill;
- The drilling methods used, methods to remove cuttings from the hole, spoil volumes, rates of advancement and daily production rates;
- Hole stability during construction and the use of casings;
- Cleanliness of the drill hole;
- Types, lengths, and dimensions of bars or tendons;
- Volumes and locations of control density fill (CDF), concrete, and grout placed; and
- Caving or heave during construction.

The GSI or a QAI shall verify and document compliance of grout types used, mix designs, and batching/mixing equipment; and monitor and record grout pressures and volumes. The report



I-405 Renton to Bellevue Widening and Express Toll Lanes Renton to Bellevue, WA November 30, 2021 WSDOT Contract No. 9242 Terracon Project No. 81205144

may be prepared by the GSI or a representative of QA. The GSI shall review the information on a daily basis and the document shall be certified as complete and accurate.

The following field tests shall be performed under the direction of a GSI or a QAI:

- All verification, performance, and proof tests of soil nails (all types) and ground anchors (all types) per article 6-15.3(8) Soil Nail Testing and Acceptance, of the WSDOT (2016) Standard Specification.
- All results of verification, performance and proof tests of soil nails shall be provided to the EOR for review. The EOR will determine final acceptance of each soil nail.

Observance of planned test pit. The purpose of the planned test pit is to evaluate the material properties of the material behind the soil nail wall and to evaluate the stand-up time of the cut when left open. The test pit will be left open for 24 hours in accordance with GDM Section 15.3.4.2.1 Soil Nail Walls. The excavation of the test pit and condition of the cut walls shall be observed by the GSI or representative of the GER.

#### 10.0 USE OF THIS REPORT

This geotechnical report has been prepared to support the design of Retaining Wall 6.50L. The analyses and recommendations presented in this report are based on the data obtained from the borings performed at the indicated locations and from other information discussed in this report. This report does not reflect variations that may occur between borings, across the site, or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until construction. If variations appear, we should be immediately notified so that further evaluation and supplemental recommendations can be provided.

This report has been prepared for the exclusive use of Parsons, FlatIron-Lane JV, and WSDOT and has been prepared in accordance with generally accepted geotechnical engineering practices. No warranties, either express or implied, are intended or made. In the event that changes in the nature, design, or location of the project as outlined in this report are planned, the conclusions and recommendations contained in this report shall not be considered valid unless Terracon reviews the changes and either verifies or modifies the conclusions of this report in writing.

#### 11.0 REFERENCES

American Association of State Highway and Transportation Officials (AASHTO) (2017). AASHTO LRFD Bridge Design Specifications (8<sup>th</sup> edition). Washington, DC. (BDS)

Boulanger, R. W. and Idriss, I. M., (2014), CPT and SPT based liquefaction triggering procedures: Davis, Calif., University of California Davis, report no. UCD/CGM-14/01, 134 p.



I-405 Renton to Bellevue Widening and Express Toll Lanes ■ Renton to Bellevue, WA November 30, 2021 ■ WSDOT Contract No. 9242 ■ Terracon Project No. 81205144

Cetin, K. O.; Seed, R. B.; Der Kiureghian, Armen; and others, (2004), Standard penetration test-based probabilistic and deterministic assessment of seismic soil liquefaction potential: Journal of Geotechnical and Geoenvironmental Engineering, v. 130, no. 12, p. 1314-1340.

FHWA (2011). GEC No. 3: LRFD Seismic Analysis and Design of Transportation Geotechnical Features and Structural Foundations.

FHWA (2015). GEC No. 7: Soil Nail Walls Reference Manual.

Galster, R.W., and W.T. Laprade. 1991. Geology of Seattle, Washington, United States of America. Bull. of the Association of Engineering Geologists, v. 28, no. 3, p. 235–302

GeoEngineers, Inc. (2008). Geotechnical Engineering Services I-405 112th Avenue SE to SE 8th Street Widening Project, Bellevue, Washington. File No. 0180-197-01. July

Project Geotechnical Soil Properties Methodology, FLJV & Wood (GSPM)

Troost, K.G. (2012). Geologic Map of Bellevue, Washington. GeoMap Northwest Production Map. April.

WSDOT (February 1, 2016) I-5/SR16 project Request for Proposal (RFP).

Appendix G4 Reference\_Info20181214

Appendix G4 ReferenceInfoBridgeSeismic20181214

WSDOT (December 14, 2018a) Geotechnical Baseline Report, I-405 Renton to Bellevue Widening and Express Toll Lanes Project. XL-4653/XL-5467, I-405, MP 0.0–14.6.

WSDOT (December 14, 2018a) Geotechnical Data Report, I-405 Renton to Bellevue Widening and Express Toll Lanes Project. XL-4653/XL-5467, I-405, MP 0.0–14.6.

WSDOT (December 14, 2018b). General Geologic Characterization and Unstable Slope Evaluation, I-405 Renton to Bellevue Widening and Express Toll Lanes Project.

WSDOT (July, 2019a). Geotechnical Design Manual (GDM).


WSDOT (July, 2019b). Bridge Design Manual (GDM).

WSDOT (2018c). Standard Specifications for Road, Bridge, and Municipal Construction.

Yount, J.C., J.P. Minard, and G.R. Dembroff. (1993). Geologic Map of Surficial Deposits in the Seattle 30' X 60' Quadrangle, Washington. USGS Open-File Report 93-233.



# APPENDIX A RETAINING WALL PLANS





# APPENDIX B BORING LOGS

HWY Form 351-003 (H. F. 26.66) (Revised 5-67).

# WASHINGTON STATE HIGHWAY COMMISSION DEPARTMENT OF HIGHWAYS

Original to Materials Engineer Copy to Bridge Engineer Copy to District Engineer

Copy to ......

#### LOG OF TEST BORING

S.HS.R. 405 Section	SR-169 O-xing to SR-90 O-xing	Job NoL-6233
Hole No. H-2 Sub Section	N.E. 30th St. U-xing Replacement	Cont. Sec. 1744
Station 0+80 W	Offset 28' N, <u>£</u>	Ground El. 2241
Type of Boring Jet and Chop	Casing 3" I.D., -47.0'	W.T. El See bottom, Sheet
	Date Dec. 18, 1979	

Inspect	tor	Jam	es l	D. Lance		Date Dec. 18, 1979 Sheet 1 of 3
DEPTH	BLOWS PER FT.	PROF	ILE	SAMPLE TUBE NO	S.	DESCRIPTION OF MATERIAL
	<u>.</u>	•			STD PEN	Sod. Dark brown organic, sandy clayey SILT. Loose, brown, gravelly silty SAND.
	27			11 A S	EN EN	Dense, brown, silty, fine to medium grained SAND - moist.
• •		-	. [	14 <b>1</b> 2	!	
5 .		-				
•		-	. <u> </u>			
					TD EN	Dense, light brown, silty, fine to medium grained SAND - moist.
	40		,	19   21 <b>V</b> 3		bensey right brown, stray, rine as measure granted arms make
10					· 	
•				•		
		<u> </u>	. <u>]</u>		TD	
•	54	1		31 P 33   37 <b>¥</b> 4	EN	Very dense, brown, silty, fine to medium grained SAND - moist.
15					•	
					TD	
	47	.	٠.	24 P	EN	Dense, brown, silty, moist, fine to medium grained SAND - piece of fine gravel in top of sample.
20				20 7 5		

DEPTH	BLOWS PER FT.	PROFILE	SAMPLE TUBE NOS.	DESCRIPTION OF MATERIAL
			Ū U−6	No Recovery - Lost Ball Valve.
25			10 A STD	Medium dense, brown, moist, very silty fine SAND - with a trace
	19		9 11 <b>Y</b> 7	of medium to coarse sand.
			A A B U-8	   Very stiff, light brown, fine sandy SILT - contains fine gravel
	·	•	C Y STD	
	12	<b>A</b>	6 PEN	Stiff, light brown, fine sandy SILT - with thin lenses of rust
30	· ••		6 <b>Y</b> 9	brown silt, moist.
•		-1		
· · · · · ·		. •	14 ♣ STD	Very hard, light brown, moist, fine sandy SILT - contains grave
	66		49 PEN	
35	٠.		<del>127 <b>†</b> 10</del>	
		-1		
		1	·	
	151		65 <b>A</b> STD 47 PEN	Very dense, brown, moist, very silty, fine to coarse SAND -
	131		104 7 11	with gravel (Glacial Till).
40			·	
	,	<b>\</b>	•	
		4		
			58 STD PEN	Very dense, light brown, slightly silty, fine to medium grained
	164		100 12	SAND - moist.
45				·

DEPTH	BLOWS PER FT.	PROFILE	SAMPLE TUBE NOS.	DESCRIPTION OF MATERIAL
		•		
47		A		
	195 10"	<u> </u>	95 ★ STD 100 ♥ PEN	Very dense, brown, moist, very silty, fine to coarse SAND -
			4" 13.	with gravel (Glacial Till).
	•			TEST BORING STOPPED AT -47.9' BELOW GROUND ELEVATION.
				WATER LEVEL READING MADE WHILE PULLING CASING: -32.0'.
	·			
		-	·	
		•		
·				
	·			
			-	
		'		

F 26 66 (Rev. 5:67)

# WASHINGTON STATE HIGHWAY COMMISSION DEPARTMENT OF HIGHWAYS

Origi	nal	to Mat	erials	Engine
Copy	to	Bridge	Engin	cer
Сору	to	District	Engi	necr

S.II. S.R. 3-4 Section 12 30 77 / STRUCTURE Job No. 6 19.76

Sub Section 12 2 Cont. Sec.

Cont. Sec.

Ground El. 211.3 '

ype of Boring 19.75 Casing 10 X 17.5 ' W.F. El. -6.0 '

spector D. J. Date 3-4-81 Sheet of 1

aspect	tor2	نل	<b></b> .	Date 3 7 0/ Sheet / of /
P 15	BLOWS PER FT.	PROFILE	SAMPLE TUBE NOS.	DESCRIPTION OF MATERIAL
		·		
		[		
				FOOTING EL. 205.0'
5		.	1.0'R	c. O. G.
	P-1 16		1 4 8	SAND: grey fines/5/27y damp
			8 V 10	
			イ.5 / Ac.	SATURATED -6.0' TO -10.5'
	9-2 16	<u> </u>	7 9	<u>.</u>
10	P- 3		1.8 F	c. SILTibr. sandy, occ. Plece of fine
	10		4	gravel WET TO -10.5' Then Damp.
			V 8 /. 8'	
	J <sup>2</sup> - 4		T 5	(YEC.
	12		6	Very Sondy
15	<i>P</i> /-		¥ 7 / / / / / / / / / / / / / / / / / /	c. 0x1d12.d -15.5'To -15.9
9	1.5 57	$\star$	33	
•			<del>  2    </del>   <del>  4   2</del>     1.8'1	SANDIBE F. TO C. GRAVEITY SIZTY
	P- 6		水ノブ       33	DAMP (LIGHTLY CEMENTED)
	78		45	
		; ·	<u> </u>	IN.E. after pulling Augers -6,0'

PROJECT N	NAME _I-405 Renton to Bellevue Widening PROJECT	NUMBER 20	316		BORING NUMBER W	-80-20		
CLIENT W				ATION Re				
DATE STAF	RTED 6/4/20 COMPLETED 6/4/20	GROUNI	GROUND ELEVATION 219.6 ft NAVD88 HOLE SIZE 8 inche					
DRILLING (	CONTRACTOR Gregory Drilling	DRILL R						
DRILLING I	METHOD HSA	STATION	STATION (FT)         5646+15.75         OFFSET (FT)         23.5 L					
LOGGED B	Y Chris Lopez CHECKED BY H. Brenniman	NORTHII	NG _19	2025.752	<b>EASTING</b> _13	03039.126		
NOTES GW LEVEL (ATD) _Dry								
(f) (f) O DEPTH GRAPHIC	SOIL & ROCK DESCRIPTION		RECOVERY % (RQD)	SAMPLE TYPE NUMBER	A SPT N VALUE A  20 40 60 80  PL MC LL  20 40 60 80  □ FINES CONTENT (%) □  20 40 60 80	TESTS AND REMARKS		
-	Poorly graded SAND with silt, medium dense, yellowish bro [Fill] (SP)	wn, moist,	44	SPT-1 6 8 10	18			
_5	Becomes loose		56	SPT-2 6 10 11	21 21	MC = 6%		
10	Silty CLAY, loose, yellowish brown to brown, moist to wet, [	Qvr] (CL-ML)		5 6 4	10	<u> </u>		
<u>10</u>			89	SPT-4 3 3 4	<b>Å I ●</b> □	MC = 30% LL = 29 PL = 24 Fines = 92%		
_	Sandy SILT, dense, yellowish brown, moist, [Qvt] (ML)			ST-1				
05 15 -			100	SPT-5 11 14 18	<b>● A</b> □	MC = 14% Fines = 54%		
- - - - 	Becomes very dense					Harder drilling		
00 20						_		

PROJECT NAME 1-405 Renton to Bellevue Widening PROJECT NUMBER 20316 BORING NUMBER W-80-20 CLIENT WSDOT PROJECT LOCATION Renton, WA RECOVERY % (RQD) SAMPLE TYPE NUMBER ▲ SPT N VALUE ▲ ELEVATION (ft) DEPTH GRAPHIC LOG 20 40 60 LL -I 80 **TESTS** MC AND REMARKS SOIL & ROCK DESCRIPTION 40 60 ☐ FINES CONTENT (%) ☐ Sandy SILT, dense, yellowish brown, moist, [Qvt] (ML) (continued) 43 50/1" Bottom of borehole at 20.6 feet.

WSDOT GEOTECH DRILLING - 1405 WSDOT.GDT - 8/24/20 15:35 - C:USERSICHELSEA.FOSTERIDOCUMENTSIPROJECTWISEWORKINGDIRIWSDOTIDMS08721/1405 WSDOT - SEG. 1.GPJ



# APPENDIX C CALCULATIONS



PROJECT: I-405 Renton to Bellevue Widening and ETL Page of \_\_\_\_\_\_ of \_\_\_\_\_

JOB NO. 81215044 Date November 2021 Comp. By YY CHECKED BY: pjp

### Appendix C Report Section 1 and 2

Retaining Wall ID	6.50L			
Туре	Special Barrier/Soil Nail Wall			
Begin Soil Nail Wall	SB405 STA 5646+03.79 (33.33' LT)- Wall STA 0+82.00			
End Soil Nail Wall	SB405 STA 5647+69.58 (33.80' LT)-Wall STA 2+50.00			
Soil Nail Wall Height (ft)	3.6 to 7.3			
Soil Nail Wall Length (ft)	165			
Special Design Barrier	North and South ends of soil nail wall, limits shown on roadway plans			
Special Design Barrier Max Height (ft)	Up 3.5			
Existing Borings	H-2-79, H-2-81, W-80-20			

### Appendix C Report Section 3

ESU assigned based on the following borings.

#### **TABLE 2 - BORING SUMMARY**


Boring Number	Date Completed	Boring Depth (ft.)	Ground Surface Elevation (ft. MSL) <sup>1</sup>	Groundwater Elevation (ft. MSL)
W-80-20	6/4/2020	20.6	219.6	Dry
H-2-79	12/18/1979	47.9	224	192
H-2-81	3/7/1981	20	211.3	205.3

#### Notes:

1. Ground water assumed at EL=209 feet for design

Wall Profile with ESU on following page.

ESU-Note, Only ESU 3B used for Wall Design ESU 1 and 3B as overburden





PROJECT: 1-405 Renton to Bellevue Widening and ETL Page \_\_\_\_\_ of \_\_\_\_\_

JOB NO. 81215044 Date November 2021 Comp. By YY CHECKED BY: pjp

### Appendix C Report Section 4 Seismic Design

#### **TABLE 3 - SEISMIC DESIGN PARAMETERS**

Parameter	Value
Site Class	D
Peak Ground Acceleration (PGA)	0.425g
FPGA	1.175
Site-Adjusted Peak Ground Acceleration (AS)	0.50
Mean Magnitude Earthquake (Mw)	7

#### **Determination of As**

The site adjusted seismic acceleration, As, was determined in accordance with GDM Chapter 6 as shown in the attached analysis. A site peak ground acceleration, PGA, of 0.433g and an earthquake magnitude of 7 were developed for the wall location. Based on observed soil conditions a Site Class D was assigned and the PGA adjusted per the following table:


No liquefaction assumed due to depth to groundwater and cohesive soils below wall.

Spectra output and Site Class calcs on following pages.

### $\mathbf{BEToolbox}^{^{\mathsf{TM}}}$

Spectra
Copyright ⊚ 2021, WSDOT, All Rights Reserved

Version 6.1.0 - Built on May 12 2021



WSDOT Bridge Design Manual 2014 Seismic Hazard Map, 7% probability of exceedance in 75 years

Site Coordinates (Latitude,Longitude): 5e+01° N, 1e+02° W

Site Soil Classification: Site Class D - Stiff Soil

Seismic hazard maps are for sites at the boundary of Site Classes B and C, which is  $\overline{v}_s = 2500$  ft/s (760 m/s). Adjustments for

other Site Classes are made as needed.

Period (sec)	Sa (g)	
0.0	0.433	PGA - Site Class B/C Boundary
0.2	0.987	S <sub>s</sub> - Site Class B/C Boundary
1.0	0.283	S <sub>1</sub> - Site Class B/C Boundary

Values of Site Coefficient,  $F_{pqa}$ , for Peak Ground Acceleration

Site Class	Mapped Peak Ground Acceleration Coefficient (PGA)							
	PGA≤ 0.10	PGA= 0.20	PGA= 0.30	PGA= 0.40	PGA= 0.50	PGA≥ 0.60		
Α	0.8	0.8	0.8	0.8	0.8	8.0		
В	0.9	0.9	0.9	0.9	0.9	0.9		
С	1.3	1.2	1.2	1.2	1.2	1.2		
D	1.6	1.4	1.3	1.2	1.1	1.1		
Ē	2.4	1.9	1.6	1.4	1.2	1.1		

For Site Class D,  $F_{pga} = 1.167$ 

Values for Site Coefficient, Fa, for 0.2 sec Period Spectral Acceleration

Site Class	Mapped S	Mapped Spectral Acceleration Coefficient at Period 0.2 sec (S <sub>s</sub> )									
	S <sub>s</sub> ≤ 0.25	S <sub>s</sub> = 0.50	S <sub>s</sub> = 0.75	S <sub>s</sub> = 1.00	S <sub>s</sub> = 1.25	S <sub>s</sub> ≥ 1.50					
Α	0.8	0.8	8.0	0.8	8.0	8.0					
В	0.9	0.9	0.9	0.9	0.9	0.9					
С	1.3	1.3	1.2	1.2	1.2	1.2					
D	1.6	1.4	1.2	1.1	1.0	1.0					
Е	2.4	1.7	1.3	1.0	0.9	0.9					

For Site Class D,  $F_a = 1.105$ 

Values of Site Coefficient,  $F_v$ , for 1.0 sec Period Spectral Acceleration

Site Class	Mapped S	Mapped Spectral Acceleration Coefficient at Period 1.0 sec (S <sub>1</sub> )								
	S <sub>1</sub> ≤ 0.1	S <sub>1</sub> = 0.2	S <sub>1</sub> = 0.5	S <sub>1</sub> ≥ 0.6						
Α	0.8	0.8	0.8	0.8	0.8	0.8				
В	0.8	0.8	0.8	0.8	0.8	0.8				
С	1.5	1.5	1.5	1.5	1.5	1.4				
D	2.4	2.2	2.0	1.9	1.8	1.7				
Е	4.2	3.3	2.8	2.4	2.2	2.0				


For Site Class D,  $F_v = 2.033$ 

$$\begin{split} & A_{\rm S} = F_{\rm pga} \; {\rm PGA} = (\; 1.167)(\; 0.433g) = 0.505g \\ & S_{\rm DS} = F_{\rm a} \; S_{\rm s} = (\; 1.105)(\; 0.987g) = 1.090g \\ & S_{\rm D1} = F_{\rm v} \; S_{\rm 1} = (\; 2.033)(\; 0.283g) = 0.576g \\ & T_{\rm o} = 0.2T_{\rm s} = (0.2)(\; 0.528) = 0.106 \; {\rm sec} \\ & T_{\rm s} = S_{\rm D1}/S_{\rm DS} = (\; 0.576)/(\; 1.090) = 0.528 \; {\rm sec} \end{split}$$

Partitions for Seismic Design Categories A, B, C, and D

S <sub>D1</sub>	SDC	
S <sub>D1</sub> < 0.15	Α	
$0.15 \le S_{D1} < 0.30$	В	
$0.30 \le S_{D1} < 0.50$	С	
$0.50 \le S_{D1}$	D	As for Site Class D
		/ 101 One Olass D

Seismic Design Category (SDC) = D



Project Name

Renton To Bellevue

Project Number 81215044
Structure Number Wall 6.50
Boring H-2-79
Date 10/28/2021



Sample Number	Sample Top Depth	Sample Bottom Depth	Midpoint of Layer	Layer Thickness, d <sub>i</sub>	N1	N2	N3	Uncorrect N Value, N <sub>i</sub>	$d_i/N_i$
1	0	1.5	0.75	0.75				9	0.08
2	2	3.5	2.75	2				27	0.07
3	7	8.5	7.75	5				40	0.13
4	12	13.5	12.75	5				64	0.08
5	17	18.5	17.75	5				47	0.11
6	24	25.5	24.75	7				19	0.37
7	28	29.5	28.75	4				12	0.33
8	32.5	34	33.25	4.5				66	0.07
9	37	38.5	37.75	4.5				97	0.05
10	42.5	43.5	43	5.25				100	0.05
11	47	48	47.5	4.5				100	0.05

NOTE: Boring Extends to 48 ft bgs

Sum Check

**Check Your Answer** 

Average N Site Class

34 D

Table 3.10.3.1-1—Site Class Definitions

Site Class	Soil Type and Profile
Α	Hard rock with measured shear wave velocity, $\overline{v}_s > 5,000$ ft/s
В	Rock with 2,500 ft/sec $< \overline{v}_s < 5,000$ ft/s
С	Very dense soil and soil rock with 1,200 ft/sec $< \overline{v}_s < 2,500$ ft/s, or with either $\overline{N} > 50$ blows/ft, or $\overline{s}_u > 2.0$ ksf
D	Stiff soil with 600 ft/s $< \overline{v}_s < 1,200$ ft/s, or with either $15 < \overline{N} < 50$ blows/ft, or $1.0 < \overline{s}_u < 2.0$ ksf
E	Soil profile with $\overline{v}_g < 600$ ft/s or with either $\overline{N} < 15$ blows/ft or $\overline{s}_u < 1.0$ ksf, or any profile with more than 10 ft of soft clay defined as soil with $PI > 20$ , $w > 40$ percent and $\overline{s}_u < 0.5$ ksf
F	Soils requiring site-specific evaluations, such as:  Peats or highly organic clays (H > 10 ft of peat or highly organic clay where H = thickness of soil) Very high plasticity clays (H > 25 ft with PI > 75) Very thick soft/medium stiff clays (H > 120 ft)

#### Method B: $\overline{N}$ method

The average  $\overline{N}$  for the top 100 ft shall be determined as:

$$\overline{N} = \frac{\sum_{i=1}^{n} d_i}{\sum_{i=1}^{n} \frac{d_i}{N_i}}$$

where:

 $V_i$  = Standard Penetration Test blow count of a layer (not to exceed 100 blows/ft in the above expression)

Project Name

Renton To Bellevue

Project Number 81215044
Structure Number Wall 6.50
Boring W-80-20
Date 10/28/2021



Sample Number	Sample Top Depth	Sample Bottom Depth	Midpoint of Layer	Layer Thickness, d <sub>i</sub>	N1	N2	N3	Uncorrect N Value, N <sub>i</sub>	d <sub>i</sub> /N <sub>i</sub>
1	2.5	4	3.25	3.25				18	0.18
2	5	6.5	5.75	2.5				21	0.12
3	7.5	9	8.25	2.5				10	0.25
4	10	11.5	10.75	2.5				7	0.36
5	15	16.5	15.75	5				32	0.16
6	20	20.5	20.25	4.5				93	0.05

NOTE: Boring Extends to 20.5 ft bgs

Sum Check

Check Your Answer

Average N Site Class 18 D

Table 3.10.3.1-1—Site Class Definitions

Site Class	Soil Type and Profile						
Α	Hard rock with measured shear wave velocity, $\overline{\nu}_s > 5,000 \text{ ft/s}$						
В	Rock with 2,500 ft/sec $< \overline{v}_s < 5,000$ ft/s						
С	Very dense soil and soil rock with 1,200 ft/sec $< \overline{v}_g < 2,500$ ft/s, or with either $\overline{N} > 50$ blows/ft, or $\overline{s}_u > 2.0$ ksf						
D	Stiff soil with 600 ft/s < $\overline{v}_s$ < 1,200 ft/s, or with either 15 < $\overline{N}$ < 50 blows/ft, or 1.0 < $\overline{s}_u$ < 2.0 ksf						
Е	Soil profile with $\overline{v}_g < 600$ ft/s or with either $\overline{N} < 15$ blows/ft or $\overline{s}_g < 1.0$ ksf, or any profile with more than 10 ft of soft clay defined as soil with $PI > 20$ , $w > 40$ percent and $\overline{s}_g < 0.5$ ksf						
F	Soils requiring site-specific evaluations, such as:  Peats or highly organic clays (H>10 ft of peat or highly organic clay where H = thickness of soil) Very high plasticity clays (H>25 ft with PI>75) Very thick soft/medium stiff clays (H>120 ft)						

#### Method B: $\overline{N}$ method

The average  $\overline{N}$  for the top 100 ft shall be determined as:

$$\overline{N} = \frac{\sum_{i=1}^{n} d_i}{\sum_{i=1}^{n} \frac{d_i}{N_i}}$$

#### where:

V<sub>i</sub> = Standard Penetration Test blow count of a layer (not to exceed 100 blows/ft in the above expression)

Project Name

Renton To Bellevue

Project Number 81215044
Structure Number Wall 6.50
Boring H-2-81
Date 10/28/2021



Sample Number	Sample Top Depth	Sample Bottom Depth	Midpoint of Layer	Layer Thickness, d <sub>i</sub>	N1	N2	N3	Uncorrect N Value, N <sub>i</sub>	d <sub>i</sub> /N <sub>i</sub>
1	5	6.5	5.75	5.75				16	0.36
2	8	9.5	8.75	3				16	0.19
3	10	11.5	10.75	2				10	0.20
4	13	14.5	13.75	3				12	0.25
5	15	16.5	15.75	2				57	0.04
6	18	19.5	18.75	3				78	0.04

NOTE: Boring Extends to 19.5 ft bgs

Sum Check

Check Your Answer

Average N Site Class 18 D

Table 3.10.3.1-1—Site Class Definitions

Site Class	Soil Type and Profile
A	Hard rock with measured shear wave velocity, $\overline{v}_s > 5,000 \text{ ft/s}$
В	Rock with 2,500 ft/sec $< \overline{v}_s < 5,000$ ft/s
С	Very dense soil and soil rock with 1,200 ft/sec $< \overline{v}_s < 2,500$ ft/s, or with either $\overline{N} > 50$ blows/ft, or $\overline{s}_u > 2.0$ ksf
D	Stiff soil with 600 ft/s < $\overline{v}_s$ < 1,200 ft/s, or with either 15 < $\overline{N}$ < 50 blows/ft, or 1.0 < $\overline{s}_u$ < 2.0 ksf
Е	Soil profile with $\overline{v}_s < 600$ ft/s or with either $\overline{N} < 15$ blows/ft or $\overline{s}_u < 1.0$ ksf, or any profile with more than 10 ft of soft clay defined as soil with $PI > 20$ , $w > 40$ percent and $\overline{s}_u < 0.5$ ksf
F	Soils requiring site-specific evaluations, such as:  Peats or highly organic clays (H>10 ft of peat or highly organic clay where H = thickness of soil) Very high plasticity clays (H>25 ft with PI>75) Very thick soft/medium stiff clays (H>120 ft)

Method B:  $\overline{N}$  method

The average  $\overline{N}$  for the top 100 ft shall be determined as:



where:

 $V_i$  = Standard Penetration Test blow count of a layer (not to exceed 100 blows/ft in the above expression)



PROJECT: I-405 Renton to Bellevue Widening and ETL

Page of

JOB NO. 81215044 Date November 2021 Comp. By YY CHECKED BY: pjp

### Appendix C Report Section 5 Design Soil Properties

Subsurface soil profiles for the wall alignment as well as several cross sections were developed for analysis of the planned soil nail wall. Soil parameters for design were established using correlations from SPT methodology outlined in the project Geotechnical Soil Properties Methodology (GSPM) contract document. Developed ESU cross sections are included in this calculations package as well as recommended soil properties for design.

#### **ESU Groupings:**

ESU Group 1 – Fill materials, either new fill engineered fills or existing fills observed ESU Group 3 – Recent deposits not containing organics such as alluvium, recessional outwash, or lacustrine deposits


#### **Soil Parameter Development**

Applicable boring explorations near the wall location have been reviewed in accordance with the methods explained in the GSPM. USCS soil type of GW, GP, GM, GC, SW, SP, SM, SC and ML soils with little to no plasticity have been assigned internal friction angles according to the figure below and assigned within the range according to their soil type and guidance provided in the WSDOT GDM Section 5.8.3 and by Wood in the table of ESU reviewed by Terracon.

Friction angle based Bowles middle range as shown of the following sheets.

#### **DESIGN SOIL PROPERTIES**

	Moist	DRAINE	D CONDITION	UNDRAINED CONDITION		
ESU	Unit Weight (PCF)	Friction Angle (degrees)	Cohesion (PSF)	Friction Angle (degrees)	Su <sup>i</sup> (PSF)	
1B	125	35	50	35	200	
3B	125	36	0	36	0	
3E	120	32	50	0	1500	
4C	135	40	200	40	200	
Wall profile	lies entirely	within ESU 3B				





PROJECT: I-405 Renton to Bellevue Widening and ETL Page \_\_\_\_\_ of \_\_\_\_

JOB NO. 81215044 Date November 2021 Comp. By YY CHECKED BY: pjp

# Appendix C Report Section Analyses and Recommendations

### Global & Compound Stability:

The software Slide2 by Rocscience. was used for these analyses. Minimum factor of safety is 1.3 (resistance factor of 0.75) in the static case and 1.1 in the seismic (pseudo-static) case per Chapter 15 of the WSDOT GDM and Appendix G updates.

We assumed the following:

- ☐ Live Load traffic surcharge was taken to be 250 psf for static conditions
- ☐ For pseudostatic analysis the horizontal seismic acceleration coefficient is assumed to be 50 percent of As per GDM 15-4.10:

$$k_h = 0.5 * As = 0.5 * 0.5g = 0.25g$$

Results are summarized below. Slide2 output prints are attached.

#### **FACTORS OF SAFETY FOR GLOBAL STABILITY**

V 1 1	Station	Static Factor of Safety	Pseudo-Static Factor of Safety
	1+39.5	1.5	1.1
	1+54	1.6	1.1
	2+05	1.5	1.1
	2+07	1.6	1.1

#### SOIL NAIL DESIGN STA 0+82 to 1+39

Minimum Nail	Horizontal	STATIC	SEISMIC		
Length (FT)	Spacing (FT)	Nail Head Load at Face (KIPS)	Nail Head Load at Face (KIPS)		
12	5	21	21		



PROJECT: I-405 Renton to Bellevue Widening and ETL Page of

JOB NO. 81215044 Date November 2021 Comp. By YY CHECKED BY: pjp


### SOIL NAIL DESIGN STA 1+39 to 2+05


Minimum Nail	Horizontal	STATIC	SEISMIC	
Length (FT)	Spacing (FT)	Nail Head Load at Face (KIPS)	Nail Head Load at Face (KIPS)	
20	4	45	45	


- 1. Two rows of nails, rectangular patter in this section are #10, 75 KSI
- 2. Use nonstructural filler under bridge footing (unbonded zone)
- 3. Double corrosion protection required


### SOIL NAIL DESIGN STA 2+05to 2+50


Minimum Nail	Horizontal	STATIC	SEISMIC		
Length (FT)	Spacing (FT)	Nail Head Load at Face (KIPS)	Nail Head Load at Face (KIPS)		
12	5	17	17		
































Project: Renton to Bellevue - Wall 6.50L WSDOT Project No.: Terracon Project No.: 81215044 Date: October 2021 Check for



Check for sliding load from footing on back of wall

$\sigma_{vStrengthImax}$ := $4.36$ <b>ksf</b>	load from footing on back of wall $F_{hStrengthImax} = 84 \ \emph{kip}$
$\sigma_{vStrengthImin}$ := 3.47 $\pmb{ksf}$	$F_{hStrengthImin}$ := 84 $m{kip}$
$\sigma_{vServiceI} \coloneqq 3.73 \; \textit{ksf}$	$F_{hServiceI} \coloneqq 54 \; m{kip}$
$\sigma_{vExtremeI}$ :=7.93 <b>ksf</b>	$F_{hExtremeI} = 300 \ kip$
$B \coloneqq 9 \ ft$	footing width
$L \coloneqq 65 \;  extit{ft}$	footing length
$\phi_f$ := $36$ °	internal friction angle of drained soil
$V_{StrengthImax} := \sigma_{vStrengthImax} \cdot B \cdot L = 2550.6$	kip
$V_{StrengthImin} := \sigma_{vStrengthImin} \cdot B \cdot L = 2029.95$	total vertical forces
$V_{ServiceI} \coloneqq \sigma_{vServiceI} \cdot B \cdot L = 2182.05 \; kip$	
$V_{ExtremeI} \coloneqq \sigma_{vExtremeI} \cdot B \cdot L = 4639.05 \ \textit{kip}$	
$C \coloneqq 1.0$	AASHTO EQ 10.6.3.4-2
$R_{\tau StrengthI} := C \cdot V_{StrengthImax} \cdot \tan(\phi_f) = 185$	3.12 <i>kip</i> Nominal sliding resistance - Strength I
$R_{\tau ExtremeI} := C \cdot V_{ExtremeI} \cdot \tan(\phi_f) = 3370.4$	7 <b>kip</b> Nominal sliding resistance - Extreme I
$arphi_{ au}$ := $0.8$ $arphi_{ep}$ := $0.5$	AASHTO Table 10.5.5.2.2-1
$R_{ep}$ := 0 $m{kip}$	Per AASHTO 11.6.3.5, passive soil pressure shall be neglected
$R_{RStrengthI} \coloneqq \varphi_{\tau} \cdot R_{\tau StrengthI} + \varphi_{ep} \cdot R_{ep} = 1482$	2.5 <i>kip</i> Sliding Resistance
$R_{RExtremeI} \coloneqq \varphi_{ au} \cdot R_{ au ExtremeI} + \varphi_{ep} \cdot R_{ep} = 2696$	
$R_{RStrengthI}$ $ label{eq:FhStrengthImax}$ and	$R_{RExtremeI}$ , $F_{hExtremeI}$
No passive wedg	e on the soil nail wall

# SnailPlus 2021: Report Output

Copyright@2009 - 2020 Deep Excavation LLC: www.deepexcavation.com A program for the evaluation of soil nail walls. Deep Excavation LLC, Astoria, New York, www.deepexcavation.com

Project: Renton To Bellevue



Company: Terracon

Prepared by engineer: YY


File number: 1

Time: 10/29/2021 10:57:26 AM

THIS PROGRAM IS PROTECTED BY U.S. COPYRIGHT LAWS AS DESCRIBED IN THE EULA. UNAUTHORIZED COPYING IS PROHIBITED. LICENSED TO: Deep Excavation LLC BY DEEP EXCAVATION LLC UNDER SPECIFIC LICENCE. This report has printed because the user has accepted responsibility as described in the disclaimer and EULA File: N:\Projects\2021\81215044\Working Files\Calculations-Analyses\Wall 6.50L\6. Soil Nail\Snail Plus\Wall 6.50 - 1 row.SNLP

# Quick analysis summary for design section: STA 1+39.5 Static

STA 1+39.5 Static



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.66	13.09	10.41	10.49	0.714	0.167	0.066	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Type	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.66	1.5	Circle	2	239	23.555	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	18.33	0.714	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

able. basic alialysis assulliptions last	. stage
Stage conditions	Permanent structure long term
Min required FS	1.5
Method	Morgenstern-Price
Nail methods	Available shear
Surface search	Circular
Min. slice width	3ft
Tolerance	1%
Force Tolerance	10%
Initial FS0	1
MP interslice factor m	1
MP interslice factor v	1
MP initial Lamda.0	0
Soil nail analysis	Same settings on all nails
Nail stability	External-Internal
Nail shear	Ignored
FS on nail STR strength	1.8
FS on nail pullout	2
FS on facing bending	1.5
FS on facing punching	1.5
FS on bolts	1.7
FS on bearing	3

Table: Nails & max mobilized head forces

Name	Nail	α	Х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	1: N1 - #6	15	-1	222	12	0	5	2.0816	10.41

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)
1	-100	233
2	-18.38	233
3	-1	224.31
4	-1	217.52
5	60	217.52

### Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко
233	ESU 1B	1	0.43
223	ESU 3B	1	0.41
211	ESU 3E	1	0.47
206.5	ESU 4C	1	0.36

### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 1+39.5 Static

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 1+39.5 Static


Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	1: N1 - #6	15	-1	222	12	0	5	0.44	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	222	12	2	50	1	N/A	N/A	#6

### Quick analysis summary for design section: STA 1+54 Static

STA 1+54 Static



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.747	30.27	25.03	30.27	0.669	0.407	0.13	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Туре	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.747	1.5	Circle	5	231	19.417	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	45.2	0.669	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

able. basic alialysis assulliptions last	. stage
Stage conditions	Permanent structure long term
Min required FS	1.5
Method	Morgenstern-Price
Nail methods	Available shear
Surface search	Circular
Min. slice width	3ft
Tolerance	1%
Force Tolerance	10%
Initial FS0	1
MP interslice factor m	1
MP interslice factor v	1
MP initial Lamda.0	0
Soil nail analysis	Same settings on all nails
Nail stability	External-Internal
Nail shear	Ignored
FS on nail STR strength	1.8
FS on nail pullout	2
FS on facing bending	1.5
FS on facing punching	1.5
FS on bolts	1.7
FS on bearing	3

Table: Nails & max mobilized head forces

Name	Nail	α	Х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	3: N1 - #10	15	-1	220	20	0	4	4.8324	19.33
Nail 1	3: N1 - #10	15	-1	217.5	20	0	7	3.5751	25.03

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)
1	-100	227.62
2	-7.96	227.62
3	-1	224.36
4	-1	217.1
5	60	217.1

### Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко
233	ESU 1B	1	0.43
223	ESU 3B	1	0.41
211	ESU 3E	1	0.47
206.5	ESU 4C	1	0.36

### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 1+54 Static

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 1+54 Static


Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	3: N1 - #1	15	-1	220	20	0	4	1.27	6	75
Nail 1	3: N1 - #1	15	-1	217.5	20	0	7	1.27	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	220	12	2	50	1	N/A	N/A	#6
Nail 1	217.5	12	2	50	1	N/A	N/A	#6

### Quick analysis summary for design section: STA 2+05 Static

STA 2+05 Static



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.686	28.9	18.61	28.9	0.639	0.388	0.127	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Туре	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.686	1.5	Circle	5	234	24.56	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	45.21	0.639	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

rable: Basic analysis assumptions	iast stage
Stage conditions	Permanent structure long term
Min required FS	1.5
Method	Morgenstern-Price
Nail methods	Available shear
Surface search	Circular
Min. slice width	3ft
Tolerance	1%
Force Tolerance	10%
Initial FS0	1
MP interslice factor m	1
MP interslice factor v	1
MP initial Lamda.0	0
Soil nail analysis	Same settings on all nails
Nail stability	External-Internal
Nail shear	Ignored
FS on nail STR strength	1.8
FS on nail pullout	2
FS on facing bending	1.5
FS on facing punching	1.5
FS on bolts	1.7
FS on bearing	3

Table: Nails & max mobilized head forces

Name	Nail	α	Х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	3: N1 - #10	15	-1	220	20	0	4	4.4851	17.94
Nail 1	3: N1 - #10	15	-1	216.5	20	0	4	4.6516	18.61

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)
1	-100	226.22
2	-9.08	226.22
3	-1	222.1
4	-1	215.83
5	60	215.83

### Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко
233	ESU 1B	1	0.43
223	ESU 3B	1	0.41
211	ESU 3E	1	0.47
206.5	ESU 4C	1	0.36

### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 2+05 Static

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 2+05 Static


Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	3: N1 - #1	15	-1	220	20	0	4	1.27	6	75
Nail 1	3: N1 - #1	15	-1	216.5	20	0	4	1.27	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	220	12	2	50	1	N/A	N/A	#6
Nail 1	216.5	12	2	50	1	N/A	N/A	#6

# Quick analysis summary for design section: STA 2+07 Static

STA 2+07 Static



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.635	12.84	10.22	10.45	0.701	0.167	0.063	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Type	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.635	1.5	Circle	8	260	44.721	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	18.33	0.701	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

able. basic alialysis assulliptions last	. stage				
Stage conditions	Permanent structure long term				
Min required FS	1.5				
Method	Morgenstern-Price				
Nail methods	Available shear				
Surface search	Circular				
Min. slice width	3ft				
Tolerance	1%				
Force Tolerance	10%				
Initial FS0	1				
MP interslice factor m	1				
MP interslice factor v	1				
MP initial Lamda.0	0				
Soil nail analysis	Same settings on all nails				
Nail stability	External-Internal				
Nail shear	Ignored				
FS on nail STR strength	1.8				
FS on nail pullout	2				
FS on facing bending	1.5				
FS on facing punching	1.5				
FS on bolts	1.7				
FS on bearing	3				

Table: Nails & max mobilized head forces

Name	Nail	α	Х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	1: N1 - #6	15	-1	220	12	0	5	2.0444	10.22

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)
1	-100	233
2	-23.1	233
3	-1	221.95
4	-1	215.78
5	60	215.65

### Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко	
233	ESU 1B	1	0.43	
223	ESU 3B	1	0.41	
211	ESU 3E	1	0.47	
206.5	ESU 4C	1	0.36	

### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 2+07 Static

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 2+07 Static


	Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
	-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Γ	Nail 1	1: N1 - #6	15	-1	220	12	0	5	0.44	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	220	12	2	50	1	N/A	N/A	#6

# Quick analysis summary for design section: STA 1+39.5 Seismic

STA 1+39.5 Seismic



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.126	17	13.51	13.61	0.695	0.163	0.077	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Туре	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.126	1.1	Circle	2	248	32.532	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	24.44	0.695	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

Table: Basic analysis assumptions is	asi siage
Stage conditions	Extreme event, flood or seismic
Min required FS	1.1
Method	Morgenstern-Price
Nail methods	Available shear
Earthquake	ax= 0.25g, az= 0g
Seismic pressures	Mononobe-Okabe
Surface search	Circular
Min. slice width	3ft
Tolerance	1%
Force Tolerance	10%
Initial FSO	1
MP interslice factor m	1
MP interslice factor v	1
MP initial Lamda.0	0
Soil nail analysis	Same settings on all nails
Nail stability	External-Internal
Nail shear	Ignored
FS on nail STR strength	1.35
FS on nail pullout	1.5
FS on facing bending	1.1
FS on facing punching	1.1
FS on bolts	1.3
FS on bearing	2.3

## Table: Nails & max mobilized head forces

Name	Nail	α	х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	1: N1 - #6	15	-1	222	12	0	5	2.7026	13.51

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)
1	-100	233
2	-18.38	233
3	-1	224.31
4	-1	217.52
5	60	217.52

## Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top ele	ev. S	oil type	OCR	Ко
233	E	SU 1B	1	0.43
223	E	ESU 3B	1	0.41
211	i	ESU 3E	1	0.47
206.5	, E	SU 4C	1	0.36

#### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 1+39.5 Seismic

#### **GENERAL SOIL NAIL DATA**

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 1+39.5 Seismic


Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	1: N1 - #6	15	-1	222	12	0	5	0.44	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	222	12	2	50	1	N/A	N/A	#6

# Quick analysis summary for design section: STA 1+54 Seismic

STA 1+54 Seismic



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.63	31.69	26.2	31.69	0.525	0.402	0.143	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Туре	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.63	1.1	Circle	5	234	22.315	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	60.27	0.525	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

ast stage				
Extreme event, flood or seismic				
1.1				
Morgenstern-Price				
Available shear				
ax= 0.25g, az= 0g				
Mononobe-Okabe				
Circular				
3ft				
1%				
10%				
1				
1				
1				
0				
Same settings on all nails				
External-Internal				
Ignored				
1.35				
1.5				
1.1				
1.1				
1.3				
2.3				

## Table: Nails & max mobilized head forces

Name	Nail	α	х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	3: N1 - #10	15	-1	220	20	0	4	5.5493	22.2
Nail 1	3: N1 - #10	15	-1	217.5	20	0	7	3.7425	26.2

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)		
1	-100	227.62		
2	-7.96	227.62		
3	-1	224.36		
4	-1	217.1		
5	60	217.1		

## Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко
233	233 ESU 1B		0.43
223	ESU 3B	1	0.41
211	ESU 3E	1	0.47
206.5	ESU 4C	1	0.36

#### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 1+54 Seismic

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 1+54 Seismic


Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	3: N1 - #1	15	-1	220	20	0	4	1.27	6	75
Nail 1	3: N1 - #1	15	-1	217.5	20	0	7	1.27	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	220	12	2	50	1	N/A	N/A	#6
Nail 1	217.5	12	2	50	1	N/A	N/A	#6

# Quick analysis summary for design section: STA 2+05 Seismic

STA 2+05 Seismic



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.536	30.26	19.71	30.61	0.502	0.387	0.134	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Туре	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.536	1.1	Circle	5	234	24.56	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	60.28	0.502	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

Table: Basic analysis assumptions is	ast stage				
Stage conditions	Extreme event, flood or seismic				
Min required FS	1.1				
Method	Morgenstern-Price				
Nail methods	Available shear				
Earthquake	ax= 0.25g, az= 0g				
Seismic pressures	Mononobe-Okabe				
Surface search	Circular				
Min. slice width	3ft				
Tolerance	1%				
Force Tolerance	10%				
Initial FS0	1				
MP interslice factor m	1				
MP interslice factor v	1				
MP initial Lamda.0	0				
Soil nail analysis	Same settings on all nails				
Nail stability	External-Internal				
Nail shear	Ignored				
FS on nail STR strength	1.35				
FS on nail pullout	1.5				
FS on facing bending	1.1				
FS on facing punching	1.1				
FS on bolts	1.3				
FS on bearing	2.3				

## Table: Nails & max mobilized head forces

Name	Nail	α	х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	3: N1 - #10	15	-1	220	20	0	4	4.9265	19.71
Nail 1	3: N1 - #10	15	-1	216.5	20	0	4	4.8709	19.48

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)		
1	-100	226.22		
2	-9.08	226.22		
3	-1	222.1		
4	-1	215.83		
5	60	215.83		

## Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко
233	ESU 1B	1	0.43
223	ESU 3B	1	0.41
211	ESU 3E	1	0.47
206.5	ESU 4C	1	0.36

#### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 2+05 Seismic

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 2+05 Seismic


Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	3: N1 - #1	15	-1	220	20	0	4	1.27	6	75
Nail 1	3: N1 - #1	15	-1	216.5	20	0	4	1.27	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	220	12	2	50	1	N/A	N/A	#6
Nail 1	216.5	12	2	50	1	N/A	N/A	#6

# Quick analysis summary for design section: STA 2+07 Seismic

STA 2+07 Seismic



Stage	Calculation	FS	Fmax.Nails	Fmax.Nails	Fmax.Mob	STR Check	STR Check	STR Chec	Max.	Min.
Section	Status	Slope	(k)	Head (k)	(k)	Nails	Plates	Facing	Reinf.	Reinf.
Stage 0	Calculated	1.156	16.23	12.91	13.2	0.664	0.163	0.074	Yes	Yes

Fmax Nails = Maximum axial nail force in analysis.
Fmax Nail@head = Maximum axial nail force at facing (To).
Fmax.Mob = Maximum mob axial nail force from To/Tmax ratio Clouterre (Tmax)
STR Nails= Stress check for nails, Design load/Design Capacity (maintain below 1 for good design).
STR Plates= Stress check for nail plates (punching and bending).
STR Facing= Stress check for facing, Design load/Design Capacity.

Table: Analysis summary for all stages, Part 1

Stage	Analyzed	FS min	FS req. code	Туре	Xc (ft)	Zc (ft)	R (ft)	Active (deg)	Passive (deg)
Stage 0	Yes	1.156	1.1	Circle	5	254	41.309	N/A	N/A

Table: Analysis summary for all stages, Part 2

Point 1	Point 2	Crack (ft)	Design Appro	Design Case	Nail force (k)	Nail check	Support Mre	Wall Mres(k-	MEQ seismic(
N/A	N/A	N/A		Service Facto	24.44	0.664	N/A	N/A	N/A

Table: Basic analysis assumptions last stage

Table. basic analysis assumptions	idst stage
Stage conditions	Extreme event, flood or seismic
Min required FS	1.1
Method	Morgenstern-Price
Nail methods	Available shear
Earthquake	ax= 0.25g, az= 0g
Seismic pressures	Mononobe-Okabe
Surface search	Circular
Min. slice width	3ft
Tolerance	1%
Force Tolerance	10%
Initial FS0	1
MP interslice factor m	1
MP interslice factor v	1
MP initial Lamda.0	0
Soil nail analysis	Same settings on all nails
Nail stability	External-Internal
Nail shear	Ignored
FS on nail STR strength	1.35
FS on nail pullout	1.5
FS on facing bending	1.1
FS on facing punching	1.1
FS on bolts	1.3
FS on bearing	2.3

## Table: Nails & max mobilized head forces

Name	Nail	α	х	El.	Lfix	Lfree	Space	Fhead	Fhead
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(k/ft)	(k)
Nail 1	1: N1 - #6	15	-1	220	12	0	5	2.5829	12.91

Fhead= Mobilized force at nail head (facing), determined from pressures at facing.

Table: Surface point coordinates for last stage

Point	x (ft)	El. (ft)
1	-100	233
2	-23.1	233
3	-1	221.95
4	-1	215.78
5	60	215.65

## Soil type property data

Name	γtot	γdry	Φ'	c'	Su	qBond	Color
	(pcf)	(pcf)	(deg)	(psf)	(psf)	(psi)	
ESU 1B	125	125	35	50	N/A	20	
ESU 3B	125	125	36	0	N/A	20	
ESU 3E	125	125	32	50	N/A	20	
ESU 4C	135	135	40	400	N/A	20	

γtot = Total unit weight below water table

γdry = Bulk unit weight above water table

c' = Effective cohesion (in drained state for clays)

 $\Phi'$  = Effective friction (in drained state for clays)

Su = Undrained shear strength (for clays in undrained condition)

qBond = Ultimate bond resistance for soil nails

Name: Wall 6.50, pos: (50, 0)

Top elev.	Soil type	OCR	Ко
233	ESU 1B	1	0.43
223	ESU 3B	1	0.41
211	ESU 3E	1	0.47
206.5	ESU 4C	1	0.36

#### **SLOPE STABILITY ANALYSIS: SOIL NAIL RESULTS ALL STAGES**

Soil nail results for design section: STA 2+07 Seismic

**GENERAL SOIL NAIL DATA** 

Soil nails are concidered only when a slope stability analysis is performed.

TABLE DATA (major parameters)

= Soil nail axial tension force for critical failure surface (may not be the greatest)

Fmax = Maximum soil nail tension from all analyzed critical failure surfaces

CAP STR = Tensile structural design capacity for soil nail CAP GEO = Tensile geotechnical pull out resistance for soil nail

TcapGEO = Critical shear resistance for soil nail (min TC1, TC2, TC3, TC4)

TC1 = Structural soil nail shear resistance

TC2 = Shear resistance according to Clouterre TC2 criterion
TC3 = Shear resistance according to Clouterre TC3 criterion
TC4 = Shear resistance according to Clouterre TC4 criterion

TC4 C4 = Shear resistance according to Clouterre TC4 criterion for limit equilibrium approach

kS = Soil subgrade modulus reaction at failure surface-soil nail intersection point

Po = Soil lateral pressure at failure surface-soil nail intersection point
Pu = Ultimate lateral pressure at failure surface-soil nail intersection point

Lo = Flexure length for shear calculations

IxxCalc = Nail moment of inertia (adjusted for corrosion loss if assumed etc)
 SxxCalc = Nail section modulus (adjusted for corrosion loss if assumed)

t.loss = Structural thickness loss (if assumed by the user)

%STR = Structural capacity loss as a percentage (if assumed by the user)

Soil nail input data for design section STA 2+07 Seismic

Name	Nail	α	Х	El.	Lfix	Lfree	Space	Asteel	Dfix	Fy
-	Section	deg	(ft)	(ft)	(ft)	(ft)	(ft)	(in^2)	(in)	(ksi)
Nail 1	1: N1 - #6	15	-1	220	12	0	5	0.44	6	75

Header plate data

Nail	El.	Width	Thick	Fy	D open.	Studs	c studs	Waler
Number	(ft)	(in)	(in)	(ksi)	(in)	Studs	c studs	Bars
Nail 1	220	12	2	50	1	N/A	N/A	#6

#### **BEARING CAPACITY**

**Level Ground Conditions** 

Renton to Bellevue Wall 6.50L Barrier

**Calculate** 

Note: Any set of consistent units can be used

Ref: Das, "Principles of Foundation Engineering," Section 3.4

(B'<=L')

Phi, φ, (deg)=	36.0			
Phi, $\phi$ ,(rad)=	0.63			
beta(deg)=	0.0			
Load inclination from vertica				

$$Nc = 50.59$$
 Width,  $B = 2.3$   
 $Nq = 37.75$  Length,  $L = 25.0$   
 $N\gamma = 56.31$  Area = 58.25

e=	0.0
e=	0.0
D/B=	0.43

q (force/area)

B'=	2.33
L'=	25.00
Eff Area =	58.25

Q (force)

			4 0 -		
γ	D (depth)	Nq	Fqs	Fqd	F
0.0	50.59	1.07	1.17	1.00	
С	Nc	Fcs	Fcd	Fci	_

γ	D (depth)	Nq	Fqs	Fqd	Fqi			
<i>125.0</i>	1.0	37.75	1.07	1.11	1.00		5573	324601
	B (width)	γ	Νγ	Fγs	Fγd	Fγi		
1/2	2.3	125.0	56.31	0.96	1.00	1.00	7895	459857

Verification Problem, see attached photocopy Example 3.3, page 114 in DAS (1984) Principles of Foundation Engineering ultimate = FS = allowable =

13,467	784,458
1.00	1.00
13,467	784,458

#### Active & Passive Earth Pressure Coefficients -- Coulomb's Method Wall 6.50L Barrier Spreadsheet Name: RetWall, Notebook = Coulomb References: Das (1984), Principles of Foundation Engineering, eqs. 5-18, 5-24 Das (1983), Fundamentals of Soil Dynamics, eq. 9.5 & 9.41 Kramer (1996), Geotechnical Earthquake Engineering, eq. 11.21 **Active & At-Rest Earth Pressures** Unit Weight rad Friction angle 0.6283 Vertical Seismic Coeff. phi (φ)= 36.0 Gamma $(\gamma) =$ 125.0 Wall friction angle delta (δ)= 0.4147 Wall Height, H Horizontal Seismic Coeff. 0.26 23.8 Backfill angle (0 horiz) alpha (α)= 26.0 0.4538 Wall inclination (90 vert) beta (β)= 90.0 1.5708 rad deg rad sin deg sin cos beta + phi = 126.0 2.199 0.809 theta = 14.6 0.254 0.968 0.252 beta - delta = 66.2 1.156 0.915 i = 90-beta 0.0 0.000 1.000 phi + delta = 1.043 0.864 phi - theta - i = 21.4 0.374 59.8 0.931 phi - alpha = 10.0 0.175 0.174 delta + i + theta = 38.3 0.669 0.784 beta - delta = 66.2 1.156 0.915 phi - theta - alpha = -4.6 -0.080 -0.080 alpha + beta = 116.0 2.025 0.899 alpha - i = 26.0 0.454 0.899 EFP (pcf) = Ka = 0.35 P (lbs)= 0.00 Active 43.89 Kae = 1.14 $\theta = \tan^{-1} \{ \frac{\kappa_n}{1 - k_v} \}$ 0.59 Ko = At Rest 74.11 Pae (lbs)= 0.00 EFPae (pcf)= 142.68 ΔKae (net)= 0.79 E'Quake 98.79 **Passive Earth Pressure** rad Unit Weight Friction angle 0.6283 125.0 phi ( $\phi$ )= 36.0 Gamma $(\gamma) =$ 0.2073 Wall friction angle 11.9 delta (δ)= Backfill angle (0 horiz) alpha (α)= 0.0 0.0000 Wall inclination (90 vert) beta (β)= 90.0 1.5708 deg rad sin cos theta= 14.6 0.254 0.968 0.252 deg rad sin i=90-beta 0.0 0.000 1.000 beta - phi = 54.0 0.942 0.809 phi+i-theta= 50.6 0.883 0.635 0.772 delta - i + theta = beta + delta = 101.9 1.778 0.979 26.5 0.462 0.895 0.445 phi + delta = 47.9 0.836 0.742 phi+delta= 47.9 0.836 0.671 0.742 phi + alpha = 36.0 0.628 0.588 phi+alpha-theta= 21.4 0.374 0.931 0.365 beta + delta = 101.9 1.778 0.979 delta-i+theta= 26.5 0.462 0.895 0.445 alpha + beta = 90.0 1.571 1.000 alpha-i 0.0 0.000 1.000 0.000 EFP (pcf) = 6.05 6.05 Passive 756.12 Kp = ∆Kpe= -3.75 2.30 Kpe= $\cos^2(\phi - \theta - i)$ Kae = - $\sin^2\beta * \sin(\beta - \delta) * \left[ 1 + \sqrt{\frac{\sin(\phi + \delta) * \sin(\phi - \alpha)}{\sin(\beta - \delta) * \sin(\beta + \alpha)}} \right]$ $\sin(\phi + \delta) * \sin(\phi - \theta - \alpha)$ $\cos \theta * \cos^2 i * \cos(\delta + i + \theta) * | 1 +$ $\cos(\delta+i+\theta)*\cos(\alpha-i)$ $\cos^2 (\phi + i - \theta)$ $\sin^2 \beta * \sin(\beta + \delta) * \left[ 1 - \sqrt{\frac{\sin(\phi + \delta) * \sin(\phi + \alpha)}{\sin(\beta + \delta) * \sin(\beta + \alpha)}} \right]$ $\cos \theta * \cos^2 i * \cos(\delta - i + \theta) * 1 - i$ $\sin(\phi + \delta) * \sin(\phi + \alpha - \theta)$